

PSEG LONG ISLAND LLC
on Behalf of and as Agent for the
LONG ISLAND LIGHTING COMPANY d/b/a LIPA

Western Nassau Transmission Project

ENVIRONMENTAL MANAGEMENT AND CONSTRUCTION PLAN

CASE NO. 17-T-0752

[This page is intentionally blank]

Table of Contents

1.0	SITE AND PROJECT DESCRIPTION.....	1
1.1	The Certified Route.....	1
1.1.1	East Garden City Substation	2
1.1.2	Valley Stream Substation	3
1.2	Property Rights.....	3
1.3	Design Criteria	3
1.4	Fulfillment of Certification Conditions.....	4
1.4.1	Conditions of the Order.....	4
1.4.2	Public Health and Safety	6
1.4.3	Environmental Management and Construction Plan.....	7
1.4.4	Notices and Public Complaints	12
1.4.5	Construction, Operation, Maintenance, and Restoration.....	15
1.4.6	Environmental Supervision.....	16
1.4.7	Roads and Highways.....	19
1.4.8	Cultural Resources	20
1.4.9	Terrestrial and Wildlife Resources.....	22
1.4.10	Petroleum and Hazardous Substances.....	22
2.0	PROJECT PERSONNEL.....	24
2.1	PSEG Long Island.....	24
2.1.1	Project Manager	24
2.1.2	Construction Project Manager.....	24
2.1.3	Construction Supervisor	25
2.1.4	Engineering Manager	25
2.1.5	Environmental Compliance Manager.....	25
2.1.6	Environmental Monitor	26
2.1.7	Traffic Supervisor	26
2.1.8	Health and Safety Manager	27
2.2	Contractors	27
2.2.1	Safety Supervisor	27
2.3	Staffing Requirements for East Garden City Substation.....	27
2.3.1	Qualified Environmental Professional	28
2.3.2	Competent Person	28

3.0	PROJECT PROCEDURES.....	29
3.1	Worksite Health and Safety	29
3.1.1	Required Orientations	29
3.1.1.1	Site Specific Safety Orientation.....	29
3.1.1.2	Project Orientation.....	29
3.1.2	Stop Work Procedures	30
3.1.3	Traffic Safety	30
3.1.4	Maintenance and Protection of Traffic Plan	30
3.1.5	Road Closures	32
3.1.6	Sidewalk Closures and Pedestrian Safety	32
3.1.7	Construction Vehicles Use of Roads	33
3.1.8	Consultation with Transportation Agencies.....	33
3.2	Soil Handling and Disposal Plan	33
3.2.1	Soil Evaluation.....	33
3.2.2	Soil Reuse	35
3.2.3	Soil Storage.....	36
3.2.4	Soil Handling, Transportation and Disposal.....	36
3.3	Spill Prevention and Response	37
3.4	Reporting Requirements	39
3.4.1	Monthly Inspection Report	39
3.4.2	Environmental Inspection Reports.....	39
3.4.3	Weekly Status Reports.....	39
3.4.4	SWPPP Weekly Inspection.....	40
4.0	ENVIRONMENTAL PROTECTION AND MITIGATION	42
4.1	Vegetation and Animal Management	42
4.1.1	Vegetation Management	42
4.1.2	Rare, Threatened, and Endangered Species	42
4.1.3	Invasive Species.....	43
4.2	Water Resources	44
4.2.1	Surface Water Resources	44
4.2.2	Groundwater and Dewatering	44
4.3	Sensitive Land Uses.....	46
4.4	Cultural Resources.....	47

4.5	Recreational Areas	47
4.6	Historical Areas.....	47
5.0	SOIL AND EROSION CONTROL.....	49
5.1	Storm Water Pollution Protection Plan	49
6.0	STANDARD CONSTRUCTION PRACTICES.....	51
6.1	Construction Equipment and Staging.....	51
6.1.1	Laydown Yards	51
6.1.2	Fusing and Conduit Staging Areas.....	52
6.1.3	Material Delivery	52
6.2	Site Security	52
6.3	Construction Time Restrictions.....	53
6.4	Construction Worker Parking Areas	53
6.5	Snow Removal and Winter Procedures.....	53
6.6	Pre-Construction.....	54
6.7	Construction	54
6.8	Post-Construction.....	55
6.9	Splice Vault Installation	55
6.10	Fiber Handhole Installation.....	56
6.11	Trenching	56
6.11.1	Trench Width and Cover Requirements.....	57
6.11.2	Compatibility with Existing Utilities	57
6.12	Duct Bank Installation.....	58
6.13	Cable Installation.....	59
6.14	Cable Splicing	60
6.15	Trenchless Installation.....	60
6.15.1	Auger Bore	60
6.15.2	Horizontal Directional Drilling	61
6.16	Stream Crossing	61
6.16.1	Contingency Plan	62
6.17	Fuel, Oil and Chemical Storage Handling.....	62
6.18	Fugitive Dust Control.....	64
6.19	Pesticides and Herbicides.....	64
6.20	Clean-Up and Restoration	65

6.20.1	Removal of Construction Materials.....	66
6.20.2	Access and Buffers	66
6.20.3	Roadway Restoration.....	66
6.20.3.1	Paving Replacement.....	66
6.20.3.2	Curbs and Sidewalks.....	66
6.21	Testing and Commissioning	67
7.0	PLAN AND PROFILE DRAWINGS.....	68

List of Appendices

- Appendix A: Plan and Profile Drawings
- Appendix B: Maintenance and Protection of Traffic Plan
- Appendix C: Stormwater Pollution Prevention Plan
- Appendix D: WNTP Tree Management Plan
- Appendix E: WNTP Invasive Species Management Plan
- Appendix F: NYSDOT Standard Specifications
- Appendix G: WNTP Supervisors Inspection Report
- Appendix H: WNTP Outreach Plan
- Appendix I: EM&CP Filing Notice